Dynatest: Rapid Pavement Tester









Trailer length = 31 ft Total length = 43 ft

- Measurements using line lasers
- Climate controlled trailer
- Integrated calibration system
- Data correlation with FWD
- Axle load range 13–22 kips
- Deflection measurements with Lasers
- Optional Measurements:
- Pavement Imaging
- Profiling
- GPR

RAPTOR Applications

- Network level structural pavement evaluation at traffic speed
- Identify areas of concern
- Structural indexes



- Better performance prediction models for pavement management
- Limit lane closures / Reduce user costs / Safety











Custom Built Trailer








Gocator 2340 Line Lasers




1280 distance

measurements



















Carbon beam carrying 12 lasers



- Dynatest delivered RAPTOR presentations at 18 state DOTS.
- Collected pavement deflection data with RAPTOR on state designated routes.
- Tested NCAT Pavement Test Track and Lee Rd.
- Below charts are from NCAT sections and various states (states are not identified for confidentiality).



- Performed NCAT Data collections at different testing variables:
 - 8 different driving speeds; (5 mph, 15 mph, 25 mph, 35 mph, 40 mph, 45mph, 50mph, 55mph) in addition to a "stopgo" run.
 - Five different load levels between approximately 13.0 kips to 22.0 kips were utilized
 - Findings of this experiment will be presented and published on TRB 2020



NCAT Pavement Test Track




NCAT Pavement Test Track was tested in June 2019.



RAPTOR Testing on the NCAT Track




The graph below shows RAPTOR based deflection basin (average of three runs at 40 mph)



RAPTOR Deflection Basin NCAT Test Track




The graph below shows the D0 measurements of 3 RAPTOR runs all at 40 mph



Repeatability of RAPTOR Runs, NCAT Sections N1-N13, 40 mph



The graph below shows the D0 measurements of 3 RAPTOR runs all at 40 mph




Repeatability of RAPTOR Runs, NCAT Sections S1-S13, 40 mph






The graph below shows Comparison between D0 from FWD at 12,000 lb. and the average D0 from three RAPTOR Runs at 40 mph







The graph below shows Comparison between D0 from FWD at 12,000 lb. and the average D0 from three RAPTOR Runs at 40 mph




FWD vs RAPTOR, NCAT Sections S1-S13, 40 mph

Structural Number Comparison



The graph below shows Comparison between SN from FWD and SN from RAPTOR, North Tangent




FWD SN vs RAPTOR SN, NCAT Sections SN-N13

Structural Number Comparison



The graph below shows Comparison between SN from FWD and SN from RAPTOR, South Tangent




FWD SN vs RAPTOR SN, NCAT Sections S1-S13





The graph below shows Comparison between RAPTOR D0 at Different Speeds



RAPTOR D0 at Different Speeds

NCAT, Lee RD (US159)




Dynatest®



RAPTOR Testing on Lee RD (US 159)

The graph below shows RAPTOR based deflection basin (average of two runs at 20 mph)

Lee RD. Northbound




RAPTOR Deflection Basin Lee RD, Northbound



RAPTOR Testing on Lee RD (US 159)

The graph below shows RAPTOR based deflection basin (average of three runs at 20 mph)






RAPTOR Deflection Basin Lee RD, Southbound



The graph below shows the D0 measurements of 2 RAPTOR runs at 20 mph




RAPTOR Repeatability, Lee RD, Northbound





The graph below shows the D0 measurements of 3 RAPTOR runs at 20 mph

Lee RD. Southbound




RAPTOR Repeatability, Lee RD, Southbound

Comparison With FWD Data



The graph below shows Comparison between D0 from FWD at 12,000 lb. and the average D0 from 2 RAPTOR Runs at 20 mph




FWD vs RAPTOR, Lee RD, Northbound

Comparison With FWD Data



The graph below shows Comparison between D0 from FWD at 12,000 lb. and the average D0 from 3 RAPTOR Runs at 20 mph




FWD vs RAPTOR, Lee RD, Southbound

In addition to testing at NCAT,

- Below are Pavement Deflections obtained by RAPTOR testing from various state designated routes.
- States are not identified for privacy.



Project Location (I-20)







Project Overview

- This section of I-20 has 3 lanes in each direction, and the pavement structure is full-depth asphalt (averaging approximately 12.5 in of asphalt concrete).
- The state DOT conducted Falling Weight Deflectometer (FWD) testing on this section in April 2018. RAPTOR testing was in March 2019.
 - FWD testing was conducted in Lanes 1 and 3, in both directions. The middle lane was not tested due to safety reasons.
 - FWD testing was conducted at approximately 250 ft. intervals, with 4 recorded load-levels (6, 9, 12 and 16 kips) at each test location.




RAPTOR Testing Effort

- RAPTOR Data Collection Specifics
 - 3 repeat runs in Lane 3, in both Eastbound and Westbound directions
 - 1 run in Lane 2, in both Eastbound and Westbound directions
 - Testing speed of 50mph
- Extra data was collected 4 miles beyond the project limit in the West direction (to MP 30.4)
- RAPTOR data presented here has been averaged at 100 ft. intervals, and all deflections have been normalized to 9,000 lbs.




The graph below shows RAPTOR based deflection D0 from 3 repeat runs



D0, Eastbound Lane 3


Note: There is a gap in the Run-1 data (near MP 42.5) as we entered the weight station. In Runs 2 and 3, we drove continuously on the Interstate without entering the weight station





Detail, Presented in 2-mile intervals






Detail, Presented in 2-mile intervals




The graph below shows RAPTOR based deflection D60 from 3 repeat runs



D60, Eastbound Lane 3



The graph below shows RAPTOR based deflection D0 from 3 repeat runs




D0, Westbound Lane 3

Comparison of RAPTOR data with 2018 FWD Data



Eastbound Lane 3




FWD D0 vs. RAPTOR D0 (Run-2), Eastbound Lane 3

Note: RAPTOR Run 2 was selected for this graph as Run 1 had a gap (near MP 42) due to entering the weight station

Comparison of RAPTOR data with 2018 FWD Data



Eastbound Lane 3




FWD D36 vs. RAPTOR D36 (Run-2), Eastbound Lane 3

Comparison of RAPTOR data with 2018 FWD Data



Eastbound Lane 3




FWD D60 vs. RAPTOR D60 (Run-2), Eastbound Lane 3

Dynatest® Pavement Expertise in Action

Comparison of RAPTOR data with 2018 FWD Data

Westbound Lane 3



FWD D0 vs. RAPTOR D0 (Run-1), Westbound Lane 3


Project Location (I-35) MP 222 to MP 250








I-35 Main Lanes NB RAPTOR Data



RAPTOR D0, NB 3 lanes (300ft Interval)




I-35 Frontage SB Road RAPTOR Data



RAPTOR D0, Frontage Rd SB 2 lanes (300ft Interval)




I-35 Frontage NB Road RAPTOR Data




RAPTOR D0, Frontage Rd NB 2 lanes (300ft Interval)

Project Location Burnet RD (Austin)






Burnet RD NB Lane 1 FWD Vs RAPTOR



RAPTOR D0 Vs FWD D0, Burnet Rd NB lane 1




Burnet RD SB Lane 1 FWD Vs RAPTOR



RAPTOR D0 Vs FWD D0, Burnet Rd SB lane 1




Burnet RD NB Lane 2 FWD Vs RAPTOR






Burnet RD SB Lane 2 FWD Vs RAPTOR






Burnet RD Structural Vs Functional



Burnet Rd Functional Vs Structural Condition


Project Location (US90/SR10)





RAPTOR Results


US90 WB - Deflection D0






RAPTOR Results








US90 EB - Deflection D0






Comparison with FWD Data

US90 WB - Deflection D0



Project Location (US 229 NB)









RAPTOR Results

The Figure below shows the full RAPTOR deflection basin on US 229 Northbound (Run1)







The Figure below shows the repeatability of two RAPTOR runs on US 229 Northbound (D0)

























The Figure below shows the repeatability of two RAPTOR runs on US 229 Northbound (D36)





Comparison with FWD Measurements


The Figure below shows comparison of RAPTOR run1 and FWD on US 229 Northbound (D0)






Comparison with FWD Measurements

The Figure below shows comparison of RAPTOR run1 and FWD on US 229 Northbound (D36)




•
$$SCI = \frac{SN_{eff}}{SN_{req}}$$


- where,
- SCI= Structural Condition Index;
- SN_{eff} = the existing (estimated) Structural Number; and
- SN_{req}= the required Structural Number.



Example of a Modified Decision Tree (Louisiana)



Example of a Modified Decision Tree (Louisiana)



Example of Pavement Performance SCI Relationship

Note

• Deflection data shown in the above slides has not been corrected/adjusted to any particular reference temperature. With temperature adjustment, a better correlation may be possible.



Conclusion

- In general, the RAPTOR based deflection data shows excellent repeatability and good correlation with FWD
- Accurate line lasers minimize texture issues experienced in former TSDDs
- Image correlation process solves the problem of measuring the same spot twice
- The deflections under the line lasers can be deduced directly from Raptor curvatures
- Deflections at other locations (ex. center deflection under the wheel) can be determined through numerical modeling



General Information

- RAPTOR testing offered as consulting engineering service
- Raw deflection data in CSV, XLS or MDB formats
 - Full deflection basin
 - Load level, surface/air temperatures
 - Data referenced to stationing accompanied by high-accuracy
 GPS data
- Backcalculated layer moduli (calibrated with layer thickness info)
- Effective structural numbers $(SN_{eff})^*$
- Reporting with presentation of data on a map



Two More RAPTOR Units are being made!!!







Omar Elbagalati, PhD, P.E. oelbagalati@dynatest.com

Dynatest®